

# EXECUTIVE SUMMARY

OF

**MEDALLIN KURBAH'S MAWLONG LIMESTONE MINE**

**For Public Hearing**

**At**

**Vill- Mawlong, Mawlong Sirdarshhip,**

**District: East Khasi Hills, State: Meghalaya**

**Lease Area: 0.266 ha.**

**Applicant: Smt. Medallin Kurbah**

**Address: Village- Marbisu, Mawsmmai**

**Distt: East Khasi Hills, State: Meghalaya**

**Environmental Consultant**

**INDIAN MINE PLANNERS & CONSULTANTS**

**GE-61, RAJDANGA MAIN ROAD**

**BEHIND VIVANTA HOTEL, EM- BYEPASS**

**KOLKATA (WEST BENGAL)**

**PIN- 700107**

**(QCI –NABET ACCREDITED ENVIRONMENTAL CONSULTING ORGANIZATION,**

**ACCREDITATION NO.- QCI/NABET/ENV/ACO/18/0727)**

## **EXECUTIVE SUMMARY**

---

### **Introduction**

The Project Proponent, Smt. Medallin Kurbah has applied for mining lease for minor mineral (Limestone) in her privately owned land over an area of 0.266 Ha. located at Mawlong, Mawlong Sirdarship, District-East Khasi Hills, and State- Meghalaya. The Project has been planned for a production of 12580 TPA.

In the present case the State Expert Appraisal Committee, Meghalaya (SEIAA) in its ToR meeting issued TOR letter vide no. ML/SEIAA/MIN/EKH/62/2020/4/2116 dated 20th November, 2020 for undertaking detailed EIA study for the purpose of obtaining environmental clearance in accordance with the provisions of the EIA Notification; 2006.

In order to assess to potential environmental impacts likely to arise due to proposed Limestone Mine Village-Mawlong, Mawlong Sirdarship, District-East Khasi Hills, State- Meghalaya Smt. Medallin Kurbah has retained **Indian Mine Planners & Consultants, Kolkata** to undertake Environmental Impact Assessment studies. The report envisages the assessment of the impact of various environmental components and its mitigation measures in order to minimize the adverse impacts.

## **EXECUTIVE SUMMARY**


### **Description of the Project**

The salient features of the proposed Limestone mine are as under:-

Project Name	<b>Medallin Kurbah's Mawlong Limestone Mine</b>
Location of mine	Village-Mawlong Mawlong Sirdarship District- East Khasi Hills State- Meghalaya.
Latitude	N 25°11'24.23" TO N 25°11'25.368
Longitude	E 91°41'34.62" TO 91°41'37.83"E
Topo sheet number	780/12
Land use	0.266 Ha.
Minerals of mine	Limestone
Total Mineable reserves	68000 MT
Life of mine	06 years
Proposed production of mine	12580 TPA / 42 TPD
Method of mining	Opencast, semi-mechanized
No of working days	300 days
Water demand	Total water requirement is about 2.0 KLD (0.50KLD Domestic Uses) + 0.75 KLD (Dust Suppression) & 0.75 KLD (Green Belt) from nearby water sources.
Sources of water	Water for drinking purpose will be met from nearby villages. For sprinkling & plantation water will be taken from private Tanker.
Man power	15 (Approx.)
Nearest railway station	Guwahati Railway Station at the distance of approx. 108 km in North direction.
Nearest airport	Umroi Airport is at the distance of approx. 64 km in North East Direction.
Seismic zone	Zone V


Vicinity map and study area map of the 10 km radius around the project site is presented in **Figure 1** and **2**.

## EXECUTIVE SUMMARY



**Figure 1**  
**Vicinity Map**

## **EXECUTIVE SUMMARY**



**Figure 2**  
**10 km Radius Map around the Project Site**



## **EXECUTIVE SUMMARY**

### **Basic Requirement for Proposed Project:**

Details are presented below:

<b>Sl. No</b>	<b>Requirement</b>	<b>Approx quantity</b>
1.	HLD (Diesel)	200 liters/ day
2.	Ammonium Nitrate (Explosives)	5.43 tons of rock/kg of explosive (approx)
3.	Booster cartridge (Explosives)	

### **Mining Method:**

- ❖ Semi mechanized open cast mining will be undertaken with drilling and blasting.
- ❖ The ultimate bench design will be 6\*6m, ultimate depth of mining will be 246 mRL and ultimate slope will be 45°.
- ❖ Drilling and Blasting: Drilling will be done by keeping hole diameter-32 mm, hole depth-6 m (including sub-grade drilling), spacing- 1.0 m, burden- 0.8 m followed by blasting.
- ❖ Blasting will be carried out with the help of explosive (slurry type) boosters and ANFO and Class- VI explosives (TLD, electric detonators and detonating fuse).
- ❖ Secondary drilling and blasting will not be taken up in that place for secondary breaking hydraulic rock breakers will be deployed.
- ❖ To avoid fly rock problem at the edge of the hill, light charged muffle blasting shall be under taken.
- ❖ Charges per hole are 0.125 kg of Primer, 0.45 kg per meters of blasting agent and one detonator.
- ❖ ROM from the mine will be transported to destinations.

### **Description of the Environment:**

The baseline environmental quality data for various components of environment, viz. Air, Noise, Water, Land and Socio-economic were generated during December 2019 to February 2020 in the study area covering 10 km around the proposed Limestone Mine. Other environmental data on flora and fauna, land-use pattern, forest etc were also generated through field surveys and also collected from different State Govt. Departments.

## **EXECUTIVE SUMMARY**

### **Air Environment:**

Ambient air quality was monitored at 9 locations. Results indicate that concentrations of PM<sub>2.5</sub>, PM<sub>10</sub>, SO<sub>2</sub>, NO<sub>x</sub> are well within the prescribed standards.

PM <sub>10</sub> -	55-89 µg/m <sup>3</sup>
PM <sub>2.5</sub> -	21-34 µg/m <sup>3</sup>
SO <sub>2</sub> -	4.1-7.6 µg/m <sup>3</sup>
NO <sub>x</sub> -	6.8-10.7 µg/m <sup>3</sup>

An automatic weather monitoring station was installed at the project site to record micro-meteorological data. Pre-dominant wind directions were observed in the winter season is from N, NNE & NNW.

### **Noise Environment:**

The noise levels in the study area are within the prescribed standards. Noise levels ranges from 53.6 dB (A) to 56.7 dB (A) during day time and 38.5 dB (A) to 41.6 dB (A) in the night time.

### **Water Environment:**

It has been observed that all the physico-chemical parameters and heavy metals of water samples from surface and ground water are below the stipulated drinking water standards. The pH, TDS, and Hardness of the surface water were found in range of 6.90-7.10, 107.0-111.0 mg/land 81.30-74.30 mg/lit respectively, whereas the ground water showed pH 6.90-7.30, TDS 99.0-117 mg/lit.

### **Land Environment:**

The break-up of the existing land use for the project is given below:

## **EXECUTIVE SUMMARY**

### **Breakup of Land Use**

S No.	Category	Existing (Area in Ha.)	Category	At End Of Mine Life (Area in Ha)
1	Area to be excavated	NIL	Area to be excavated	0.15
2	Storage of top soil	NIL	Storage of top soil	0.00
3	Overburden dump	NIL	Overburden dump	0.00
4	Mineral/Sub-grade stack	NIL	Mineral/Sub-grade stack	0.00
5	Infrastructure	NIL	Infrastructure	0.01
6	Roads	NIL	Roads	0.00
7	Greenbelt	NIL	Greenbelt	0.10
8	Reclamation	NIL	Reclamation	0.00
9	Others	NIL	Others	0.00
10	Unused Area	0.26		
	<b>Total</b>	<b>0.26</b>	<b>Total</b>	<b>0.26</b>

### **Soil:**

The soil quality assessment was carried out at seven locations. The bulk density of the soil in the study area ranges between 1.43 to 1.60 gm/cm<sup>3</sup>, which indicate favorable physical condition for plant growth. Variation in the pH of the soil in the study area were observed and it is found to be neutral (6.8 to 7.20), thus conducive for growth of plant. Organic carbon and nitrogen are found in the range of 0.66-0.79 % and 0.88-1.21 %. This shows that soil is moderately good in organic and deficit in nitrogen contents. Primary nutrient profile shows that soil is low in fertility due to the availability of low amount of nitrogen and potassium.

### **Flora & Fauna:**

The density of the plant in core zone in general is very low due to rocky terrain and low soil content. The floral found in the whole of the study area are representative of the Tropical Lower Montane Forest, Tropical Semi-Evergreen, Moist-Broadleaf Forest, Tropical Deciduous/Semi-Deciduous, Broadleaf Forest and Tropical Sparse trees. There are is no schedule I Species of Fauna found in both core as well as buffer zone. The main crops grown in nearby areas are Wheat, rice, potatoes and pulses.

### **Socio-economic Status:**

The study has been conducted by primary survey and secondary data



## **EXECUTIVE SUMMARY**

source from Census of India 2011.

The primary socio economic study has been conducted in villages. The results are discussed below:

- **Core Zone:** There is no habitation in the core zone
- **Buffer Zone:** The total number of Households of the study area in rural village area are 10329 as per Census 2011. The details are given below.
- **Population:**

The total population of the study area is 52787 constituting 26618 Male and 26169 Female.

- **Social Structure**

The proportion of Scheduled Caste (SC) population within the study area is 4.21 % and the percentage of schedule Tribe (ST) is 81.83%.

- **Literacy**

The total proportion of literate within the study area is 60.76% of total population. In percentage the male literacy 31.25% and the female literacy is 29.51% respectively within study area.

### **Anticipated Environmental Impact & Mitigation Measures:**

**1. Land Environment:** The proposed project of limestone mining will definitely change the land use. However the area will be reclaimed by the following measures:

- To minimize the effect of mining plantation will be in done along the 7.5m boundary of the mine area and after the exhaustion of the pit whole area will be reclaimed into green cover. After the conceptual mining there will be a mine void which will be extensively planted.
- Mining operations will be confined strictly within the demarcated area.
- During Plan period some quantity of gritty soil (6770 MT) will be removed and will be stacked in a specific stack-yard. It will be used for road maintenance and plantation.

## **EXECUTIVE SUMMARY**

---

- The dust generation due to the mining will be minimized by sprinkling of water through water sprinkler.
- No effect on public buildings or monuments is envisaged as there are no public buildings/ monuments in the close vicinity of the mining lease area.

**2. Water Environment:** Total water requirement in the proposed mining project is 2KLD. Dust suppression shall be done by collecting operational pit water collected during rain. Drinking water will be sourced by from nearby villages by water tanker. Mining will be restricted up to a depth of 24 m. There is no possibility of mining encountering any surface/subsurface water body. To avoid contamination of ground water from the open defecation by workers, toilets will be provided for the workers at site with septic tank followed by soak pit.

**3. Air Environment:** The air borne particulate matter is the main air pollutant contributed by opencast mining with drilling and blasting. Various emission sources are identified from the proposed mining operations. However the area will be reclaimed by the following measures:

- Drilling machines will be equipped with dust collector arrangement and wherever required wet drilling arrangement will be used to prevent generation and spreading of dust.
- Personnel working on the drills and other mining activities will be provided with dust mask and other necessary Personal Protective Equipments (PPE). Health checkups will be done biannually to monitor the health of the workers.
- Regular maintenance of vehicles and machinery will be done.
- Water tankers with suitable sprinkling system will be deployed along haul roads and other unworked areas to control fugitive emission.

**4. Noise Environment:** The proposed mining operations will be carried by using latest equipments by open cast semi mechanized mining method. Hydraulic excavator will be used in excavation. Hence workers will be given protective gears such as goggles, dust masks, gloves, helmets and earmuffs. Plantation will be done to create cover from high noise. Task rotation of workers will be done exposed to noise.

## **EXECUTIVE SUMMARY**

---

**5. Biological Environment:** There is no Forest area diversion is required in the proposed mining. The fauna in the vicinity of the mine is restricted to few common species. There will hardly be any negative impacts on terrestrial eco-system comprising birds and animals as the ML area is only 0.266 Ha. On the contrary, with progressive growth of greenery, terrestrial eco-system will improve in course of time. There will be no Schedule-I species found in study area.

**6. Socio- Economic environment:** The project will enhance direct and indirect employment in the area. Therefore overall economic development is much likely after the commencement of the project. The project will provide skill based training to the locals and will generate chance of indirect employment in the area.

**7. Mine Waste:** Mine waste, alluvial soil and overburden will be stacked at separate stack yard and will be use for road construction and plantation. Alluvial soil generated shall be re used for plantation. Mining shall not be done during rains and there shall be construction of retaining wall and garland drain to prevent surface runoff. Hazardous waste such as used oil shall be stored properly and sold to registered-processor. Domestic waste water due to daily human activities which shall be properly disposed off into septic tanks followed by soak pit. Other domestic solid waste such as Wrappers, foils, left- over food material etc shall be collected in separate bins. Biodegradable waste will be composted and used as manure.

**8. Impacts due to transportation:** The entire mineral will be transported to the Cement plant through trucks. Transportation shall be done by 1 no. of 10 tonner truck. As per study done there will not be any congestion due to proposed project on the road.

### **Environmental Monitoring Programme:**

The environmental monitoring is important to assess performance of pollution control equipment installed at the project site. The sampling and analysis of environmental attributes including monitoring locations will be as per guidelines of the Central Pollution Control Board/State Pollution Control Board

- Environmental monitoring will be conducted on regular basis by Smt.

## **EXECUTIVE SUMMARY**

---

Medallin Kurbah to assess the pollution level in and around the project area

- Adequate budgetary provision shall be made towards implementation of Environmental Management Plan

**Risk Assessment & Disaster Management Plan:** Mining will be carried out by semi mechanized opencast mining, with mining equipments as hydraulic excavator, dumpers etc involving drilling and blasting. Mining will be done under strict supervision hence the rate of operational risks is minimal.

**Rehabilitation and Resettlement:** There will be no rehabilitation and resettlement on account of mining. There is no human habitation at the project site and the land is deemed forest land.

**Project benefits:** The proposed mining project has a significant positive impact on the socio-economic environment and it will help sustain the overall development of the area.

The proposed project significantly contributes the economic development by providing direct employment to 15 people and indirect employment to many more people in the area.

PP will organize Camps for vocational training to generate employment.

**Environmental Management Plan:** Preparation of Environmental Management Plan (EMP) is required for formulation, implementation and monitoring of environmental protection measures during and after commissioning of the proposed mining project. The project cost is Rs.24.50 Lakh and the EMP capital cost Rs. 2.32 Lakh (Annual recurring cost).

## **EXECUTIVE SUMMARY**

### **Budgetary Provision for Environmental Measures:**

<b>Sl. No.</b>	<b>Particulars</b>	<b>Annual Recurring Cost</b>
1.	Air Pollution (dust suppression along road water sprinklers)	50000.00
2.	Plantation & Maintenance	10000.00
3.	Provision of fencing around mine pit	5000.00
4.	Personal Protective Equipment (Helmets, Safety Shoes, Dust Masks, Ear Plugs etc)	10000.00
5.	Construction & Maintenance of Settling Tank, Garland Drains etc.	30000.00
6.	Environment Monitoring (Air, Water, Noise & Soil Monitoring)	15000.00
7.	CSR activity in nearby villages	80000.00
8.	CER activity as prescribed by SEAC	32000.00
	<b>Total</b>	<b>232000.00</b>

### **Corporate Social Responsibility:**

Being a corporate citizen the company has the responsibility of contributing to the welfare of the society in which it operates. The company will organize various awareness programmes for its employee and the general public of the area where it operates to ensure a better, sustainable way of life for the weaker sections of society.

### **Budgetary Provision for CSR Activity**

<b>ACTIVITIES</b>	<b>COST (In Rs)</b>
Quarterly medical checkup camp will be organized for the villagers of the nearby villages of the applied area by a qualified Doctor (M.B.B.S.) for minimum 100 nos of villagers @ Rs 20,000/- per quarter. Total 4 x 20,000/- = Rs 80,000/-	80,000.00
To promote education by providing Books, Copies, School Dresses to the nearby village school's needy students.	22,000.00
To promote the Swachh Bharat Mission, toilets will be made	20,500.00

## **EXECUTIVE SUMMARY**

for the nearby villagers.	
<b>Total for five years i.e. 5% of project cost</b>	<b>1,22,500.00</b>

### **Occupational Health and Safety:**

Effective implementation of measures suggested for pollution control will ensure safety and health of the workers.

**Green belt development:** It has been initiated by the proponent 0.03 ha will be planted during plan period. However as per conceptual plan entire lease area will be planted. Locally thriving species will be planted in consultation with forest department.

Among other environmental protection following measures are listed below:

- Sprinkling of water for dust suppression on mine haul roads.
- Regular Compaction & grading of haul roads and service roads to clear accumulation of loose material.
- Avoid overloading of dumpers and consequent spillage on the roads.
- Good maintenance of vehicles & machinery.
- Water sprinklers of fixed type will be provided at the mine approach roads from mine face / benches to crush hopper to prevent the generation of dust.